

SCOPE OF WORK

2023 Florida Building Code, Energy Conservation, 8th Edition

Job Site Address: _____

BUILDING (INTERIOR)

- | | | |
|----------|----------|----------|
| 1. _____ | 3. _____ | 5. _____ |
| 2. _____ | 4. _____ | 6. _____ |

☒ No interior work being done.

BUILDING (EXTERIOR)

- | | | |
|--|--------------------------|------------------------------|
| 1. <u>Frame false dormer over front door</u> | 3. <u>Install soffit</u> | 5. <u>False flying gable</u> |
| 2. <u>Install fascia</u> | 4. <u>Paint exterior</u> | 6. _____ |

☐ No exterior work being done.

MECHANICAL

- | | | |
|----------|----------|----------|
| 1. _____ | 3. _____ | 5. _____ |
| 2. _____ | 4. _____ | 6. _____ |

☒ No mechanical work being done.

ELECTRICAL

- | | | |
|----------|----------|----------|
| 1. _____ | 3. _____ | 5. _____ |
| 2. _____ | 4. _____ | 6. _____ |

☒ No electrical work being done.

PLUMBING

- | | | |
|----------|----------|----------|
| 1. _____ | 3. _____ | 5. _____ |
| 2. _____ | 4. _____ | 6. _____ |

☒ No plumbing work being done.

GAS

- | | | |
|----------|----------|----------|
| 1. _____ | 3. _____ | 5. _____ |
| 2. _____ | 4. _____ | 6. _____ |

☒ No gas work being done.

ROOF

- | | | |
|--------------------------|-----------------------------|----------|
| 1. <u>Re-roof</u> | 3. <u>HDZ Arch Shingles</u> | 5. _____ |
| 2. <u>GAF Timberline</u> | 4. _____ | 6. _____ |

☐ No roofing work being done.

Created 12/2023

Parrot Scope of Work

1. The existing roof will be removed to plywood, plywood nailing will be brought to code, any rot will be replaced, two layers of underlayment will be installed, and new GAF Limited Life-Time Warranty Timberline HDZ Architectural Shingles will be installed.
2. A single false dormer will be installed over the front door. It will be attached to the top cord of the trusses using an LSTA24 strap.
3. A single flying gable will be installed over the garage. The flying gable will be attached to the top cord of the trusses using an LSTA24 strap.
4. New Hardi board will be installed on the new dormer and new gable.
5. New soffit and fascia will be installed on the new dormer and new gable.
6. The entire house is to be painted.