

16

JASON ELIXSON CONSTRUCTION LLC  
4853 WEST SR 238  
LAKE BUTLER, FLORIDA 32054  
(386)623-1741  
CBC1250331  
CCC1325779

JOB: Sistrunk

Date: 09/17/2012

### Roof Estimate

#### Included in estimate:

- Remove and dispose of existing metal eave drip
- Repair to damaged sheathing if needed (max. of 64 sq. ft.)
- Approx. 2830 sq. ft. of roof to be stripped with 1X4's 16" on center attached with screws
- New eave drip
- New valley metal
- Installation of new 26 G. rib-panels as per code
- Ridge caps
- Neoprene pipe boots
- Gable trim

#### Front porch (approx. 12X15):

- 4X4 post wrapped in Hardi-board
- Vaulted trusses
- Attachment to existing roof shall be conventionally framed
- 1/2" CDX sheathing
- 30# Felt
- Roof stripped with 1X4's
- 26 G. Rib panels
- Gable shall be covered with 4X8 Hardi-board
- Ceiling shall be 4X8 Hardi-board
- Soffit to match existing soffit on the home

#### Back porch (approx. 12X20):

- 4X6 post
- Vaulted trusses
- Attachment to existing roof shall be conventionally framed
- 1/2" CDX sheathing
- 30# Felt
- Roof stripped with 1X4's
- 26 G. Rib panels
- Gable shall be covered with 4X8 Hardi-board

- Open ceiling
- Soffit to match existing soffit on the home

No painting or electrical wiring included

Total: \$14406.00

Add ¾" foam insulation

\$845.00

Total: \$15251.00